

TTP-A-4HW-93 4 MODULE POLE TOP MOUNT

Mount 4 modules with a total area of 100 square feet or less on a 6-inch Schedule-40 or Schedule-80 pole

- 93-inch rails accommodate 4 modules with widths up to 45.5 inches
- Mounts on user-supplied 6-inch
 Schedule-40 or Schedule-80 steel pipe
- Module clamps fit frames between 30 to 40 mm deep*
- No complex sizing documents or need to send module data sheets when ordering
- Heavy-Duty steel structure and Tamarack
 3.1 aluminum module mounting rails
- Module Rails attach to 2-inch Schedule 80 steel pipe.
 Purchase this pipe locally to save shipping cost or order appropriate length separately.
 Use two 10-foot pipes for modules up to 78-inches long.
 Use two 12-foot pipes for modules up to 98-inches long.
- 10° to 60° tilt angle
- UPS Shippable in 4 boxes
- Engineered for up to 160 mph wind speed and up to 200 psf snow load
- Site specific engineering for permit packages is available for an extra fee



| TTP-A-4HW 6-inch Sch 40 Pole Module Size 43" x 78" Maximum Snow Load (PSF), Exposure B, 6-foot clearance at front edge | | | | | | | | | | |
|---|--------|--------|---------|-----|---------|-----|---------|-----|---------|---------|
| Tilt | 90 MPH | 95 MPH | 100 MPH | | 110 MPH | | 130 MPH | | 150 MPH | 160 MPH |
| 0° | 80 | 80 | 80 | 80 | 80 | 80 | 70 | 70 | 60 | 50 |
| 5° | 80 | 80 | 80 | 80 | 80 | 80 | 70 | 70 | 60 | 50 |
| 10° | 80 | 80 | 80 | 80 | 80 | 80 | 70 | 70 | 60 | 50 |
| 15° | 80 | 80 | 80 | 80 | 80 | 80 | 70 | 70 | 60 | 50 |
| 20° | 80 | 80 | 80 | 80 | 80 | 80 | 70 | 70 | 60 | 40 |
| 25° | 90 | 90 | 90 | 90 | 90 | 90 | 80 | 80 | 70 | 30 |
| 30° | 90 | 90 | 90 | 90 | 90 | 90 | 80 | 80 | 70 | 20 |
| 35° | 90 | 90 | 90 | 90 | 90 | 90 | 80 | 80 | 70 | 10 |
| 40° | 90 | 90 | 90 | 90 | 90 | 90 | 80 | 80 | 70 | X |
| 45° | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 60 | X |
| 50° | 150 | 150 | 150 | 150 | 150 | 150 | 150 | 150 | 60 | X |
| 55° | 200 | 200 | 200 | 200 | 200 | 200 | 200 | 200 | 80 | X |
| 60° | 200 | 200 | 200 | 200 | 200 | 200 | 200 | 200 | 100 | Х |
| 65° | 200 | 200 | 200 | 200 | 200 | 200 | 200 | 200 | 150 | X |

The table above shows the maximum snow load for this mount at various wind speed and tilt angles. Larger modules and higher clearance will change maximum wind and snow load.

TTP-A-4HW-93 ships without 2-inch Schedule-40 pipe - 166 lbs

PIPE-KIT-HD10 includes four 2-inch Sch-80 5 foot pipes and 2 couplings. Use with modules up 78-inches long. 104 lbs **PIPE-KIT-HD12** includes four 2-inch Sch-80 6 foot pipes and 2 couplings. Use with modules up 98-inches long. 125 lbs

Note: Pipe Kits above are shipped in 5-foot or 6-foot sections with couplings so they can ship via UPS.

*Deeper frames can be used by adding 50/50+ mounting clamps (Item# 89907, sold separately)